## Name of Work: <u>2018-19 Construction of Mini Material Recovery Collection Centre at Various</u> <u>Places.</u>

TYPE - IX (Size 2.50 x 1.60 mts.)

									IN [SILC LISO X 1100 ]	
)	10.16.1	Steel work in built up tubular (round, square or rectanglar hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes.								
		a) 50 x 25x2.60 <sup>mm</sup> Rectangular Hollow section for supporting post of roof.								
		For post (Front)	4	x	2.10	=	8.40			
		Tie beam (Length wise)	3	х	2.50	=	7.50			
		Tie beam (Width wise)	2	x	0.60	=	3.20			
			-			-	19.10 m x 2.71kg	/m	= 51.761 kg	
		b) 25x25x2.60 <sup>mm</sup> Square Hollow section for common rafters.							51/01 15	
			2x4	х	1.00	=	8.00 m x 1.69 kg/	′m	<sup>=</sup> 13.52 kg	
									= 65.281  kg	
		Say 65.50 kg					<b>Rs.</b> 1	30.07 /	kg = Rs. 8519.59	
	10.25.2	Item shifted to head 14 as item							2	

2) 10.25.2 Item shifted to head 14 as item 14.74 steel work welded in built up sections of framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in grainting, frames, guard bar, ladder, railing brackets, gates and similar works.

1)

a) 30 x 20 x 3<sup>mm</sup> angel iron frame and 5<sup>mm</sup> dia MS rods vertical and horizontal nets at 10cm c/c for compartment

Bottom row compartment	1	х	2	=	2 No.
No. of mesh pieces	4	х	5	=	20 Nos.
Top row compartment	1	х	2	=	1 No.
No. of mesh pieces	4	х	4	=	16 Nos.
1 pieces weight of mesh				=	6.023 kg.
Hence 36 Nos. (20 +16) pieces of weight	36	х	6.023	=	216.828

## Say 220.00 kg

Rs. 123.87/ kg = Rs. 27251.4 12.50 Providing and fixing precoated 3) galvanised iron profile sheets (size, shape and pitch of corrugation asapproved by Engineer-in-charge) 0.50 mm (+ 0.05 %), total coated thickness with zinc coating 120grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of thesheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 micronsminimum to avoid scratches during transportation and should be supplied in single length upto 12metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling / self tapping Roof 2.50 1 x 1.42 = 3.55 х 2 x 3.45 х 1.45 = 9.86 5.18 Say 10.00  $m^2$ Rs.  $793.24/m^2$ = **Rs.** 7932.40 Providing lock and locking 4) arrangement with name board.


LS = Rs. 2500.00= Rs. 46203.39


Total

Unforeseen	= <b>Rs.</b> 296.61	
Grand Total	= <b>Rs. 46500.00</b>	
	=========	

## Name of work - 2018-19 Construction of a Mini Material Collection Center at various places


Type No. IX (Size 2.50 X 1.60 M)





<u>PLAN</u>

## **Details of one piece of mesh**



5 MM Dia M.S. rods for net @ .085 M c/c

	Data for 1 piece of mesh in size 0.80 X 0.80 M							
(a)	30 X 20 X 3 MM Angle iron frame :-							
	Vertical Frame	-2 X 0.80 = 1.60						
	Horizontal Frame -2 X 0.80 = <u>1.60</u>							
	3.20 M X 1.10 Kg/M = 3.52 Kg							
(b)	5 MM Dia M.S. rods Vertical and Horizontal net :-							
	Vertical	- 9 X 0.80 = 7.20						
	Horizontal	- 9 X 0.80 = <u>7.20</u>						
	14.40 M X 0.154 Kg/M = <u>2.217</u> Kg							
			5.737					
		add 5 % wastage	0.286					
			<u><b>6.023</b></u> Kg					